

Internal Cost Analysis

A self-contained explanation of the saved material, labor, machine, outside-processing, and additional costs used to calculate this part price.

Part	ABC-123	Revision	B
Description	Overflow pagination example	Cost quantity	100
Cost date	2026-08-03 12:30	Reference	Costing run 42
Prepared by	report-user	Current saved cost	Yes

Cost conclusion

PRODUCTION QTY 100		RAW COST/UNIT \$18.7600		CALCULATED PRICE/UNIT \$21.9345	
Cost element	Raw cost	% raw	Effective factor	Calculated price	Price/unit
Materials	\$721.00	38.4%	1.200x	\$865.20	\$8.6520
Machine	\$630.00	33.6%	1.150x	\$724.50	\$7.2450
Labor	\$525.00	28.0%	1.150x	\$603.75	\$6.0375
Outside processing	\$0.00	0.0%	-	\$0.00	\$0.0000
Additional	\$0.00	0.0%	-	\$0.00	\$0.0000
Total	\$1,876.00	100.0%	1.169x	\$2,193.45	\$21.9345

The ERP retail reference saved with this run was \$8.9900 per unit. It is shown as a comparison only and is not used in the cost build-up above.

Costed line summary

Materials (4)

Material	Qty/part	Raw cost	Calculated price
AL-6061-1 - Aluminum round bar	1.25	\$180.25	\$216.30
AL-6061-2 - Aluminum round bar	1.25	\$180.25	\$216.30
AL-6061-3 - Aluminum round bar	1.25	\$180.25	\$216.30
AL-6061-4 - Aluminum round bar	1.25	\$180.25	\$216.30
Material lines		\$721.00	\$865.20

Costed line summary (continued)

Operations (7)

Operation	Work center	Raw cost	Calculated price
10 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
20 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
30 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
40 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
50 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
60 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
70 / OP20 - Machine profile and finish bores	MILL	\$165.00	\$189.75
Operation lines		\$1,155.00	\$1,328.25

Material cost build-up

Backflushed materials only. Source, quantity extension, and cost contribution follow for each line.

1. AL-6061-1 - Aluminum round bar

Source: PO PO-1001-1, 2026-07-15 | \$11.5360/BAR x 0.125 conversion = \$1.4420/EA.

Question	Calculation	Result
Net quantity required	1.25 per assembly x 100 assemblies	125
Purchase increment	Saved minimum/increment used for rounding	25
Quantity charged	Net required 125 + rounding/waste 0	125

Line cost: 125 x \$1.4420 = \$180.25 raw; x 1.200x = \$216.30.

Cost component	Raw cost	Factor	Calculated price
Material	\$180.25	1.200x	\$216.30
Line contribution	\$180.25	1.200x	\$216.30

2. AL-6061-2 - Aluminum round bar

Source: PO PO-1002-1, 2026-07-15 | \$11.5360/BAR x 0.125 conversion = \$1.4420/EA.

Question	Calculation	Result
Net quantity required	1.25 per assembly x 100 assemblies	125
Purchase increment	Saved minimum/increment used for rounding	25
Quantity charged	Net required 125 + rounding/waste 0	125

Line cost: 125 x \$1.4420 = \$180.25 raw; x 1.200x = \$216.30.

Cost component	Raw cost	Factor	Calculated price
Material	\$180.25	1.200x	\$216.30
Line contribution	\$180.25	1.200x	\$216.30

3. AL-6061-3 - Aluminum round bar

Source: PO PO-1003-1, 2026-07-15 | \$11.5360/BAR x 0.125 conversion = \$1.4420/EA.

Question	Calculation	Result
Net quantity required	1.25 per assembly x 100 assemblies	125
Purchase increment	Saved minimum/increment used for rounding	25
Quantity charged	Net required 125 + rounding/waste 0	125

Line cost: 125 x \$1.4420 = \$180.25 raw; x 1.200x = \$216.30.

Cost component	Raw cost	Factor	Calculated price
Material	\$180.25	1.200x	\$216.30
Line contribution	\$180.25	1.200x	\$216.30

4. AL-6061-4 - Aluminum round bar

Source: PO PO-1004-1, 2026-07-15 | \$11.5360/BAR x 0.125 conversion = \$1.4420/EA.

Question	Calculation	Result
Net quantity required	1.25 per assembly x 100 assemblies	125
Purchase increment	Saved minimum/increment used for rounding	25
Quantity charged	Net required 125 + rounding/waste 0	125

Line cost: 125 x \$1.4420 = \$180.25 raw; x 1.200x = \$216.30.

Cost component	Raw cost	Factor	Calculated price
Material	\$180.25	1.200x	\$216.30
Line contribution	\$180.25	1.200x	\$216.30

Operation cost build-up

Saved routing sequence with time and rate equations for internal work and PO pricing for outside work.

10. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

20. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

30. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

40. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

50. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

60. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

70. OP20 - Machine profile and finish bores

Work center: MILL | Demand: 1/part x 100 parts = 100 units.

Driver	Calculation	Result
Batches	Ceiling(100 processed units / 25 batch size)	4
Batch resets	Maximum(4 batches - 1, 0)	3
Running time	100 units x 0.08 cycle hr/unit	8 hr
Occupied time	1.5 setup + 8 running + 3 x (0.1 reset + 0.05 idle)	9.95 hr
After-hours idle	Saved scheduling result	0 hr

Labor: (1.5 setup hr x \$25.00/hr) + (3 resets x 0.1 hr x \$25.00/hr) = \$75.00 raw.

Machine: (9.95 occupied hr x \$5.00/hr) + (0 after-hours hr x \$5.00/hr x 1) + (8 running hr x \$10.00/hr) = \$90.00 raw.

Cost component	Raw cost	Factor	Calculated price
Machine	\$90.00	1.150x	\$103.50
Labor	\$75.00	1.150x	\$86.25
Operation contribution	\$165.00	1.150x	\$189.75

Reconciliation and review flags

This audit ties the saved header totals back to the saved material and operation lines. Non-zero variance indicates an inconsistent saved snapshot that should not be used for quoting.

Bucket	Header raw	Lines raw	Variance	Header price	Lines price	Variance
Materials	\$721.00	\$721.00	\$0.00	\$865.20	\$865.20	\$0.00
Machine	\$630.00	\$630.00	\$0.00	\$724.50	\$724.50	\$0.00
Labor	\$525.00	\$525.00	\$0.00	\$603.75	\$603.75	\$0.00
Outside processing	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
Additional	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
Total	\$1,876.00	\$1,876.00	\$0.00	\$2,193.45	\$2,193.45	\$0.00

Review flags

- No automatic source-quality flags were found in the saved lines.

Internal notes

Sample with four material lines and seven operation lines.